

Bruhat Bangalore Mahanagara Palike
Executive Engineer Dasarahalli Division

Name of Work: Improvements and Asphaltting to AGB Layout Railway parallel road and 80 feet Southern side cross roads in ward No 12, Shettyhalli Sub Division

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Civil Work								
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications								
	CC Drain								
	1st Cross frm AGB Layout mn Rd to SWD (LHS)								
	LHS	1	316.00	1.20	0.90	341.28			
	RHS	1	328.00	1.20	0.90	354.24			
	1st Cross frm AGB Layout mn (RHS Up to Dead End)								
	LHS	1	258.00	1.20	0.90	278.64			
	RHS	1	271.00	1.20	0.90	292.68			
	Marison Layout								
	Chef Bakers Road(LHS)	2	101.00	1.20	0.90	218.16			
	Bharani Medical Store Road	2	206.00	1.20	0.90	444.96			
	Culvert								
	Culvert 8th Crs	1	11.60	1.50	0.90	15.66			
	Culvert 7th Crs	1	7.50	1.50	0.90	10.13			
	Culvert 6th Crs	1	7.90	1.50	0.90	10.67			
	Culvert 5th Crs	1	7.85	1.50	0.90	10.60			
	Culvert 4th Crs	1	8.00	1.50	0.90	10.80			
	Culvert 3rd Crs	1	7.60	1.50	0.90	10.26			
	Culvert 2nd	1	6.70	1.50	0.90	9.05			
	Culvert 1st	1	7.40	1.50	0.90	9.99			
	Culvert	1	7.00	1.50	0.90	9.45			
						2026.55	Cum	220.40	446652.17
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	CC Drain								
	1st Cross frm AGB Layout mn Rd to SWD (LHS)								
	LHS	1	316.00	1.20	0.15	56.88			
	RHS	1	328.00	1.20	0.15	59.04			
	1st Cross frm AGB Layout mn (RHS Up to Dead End)								
	LHS	1	258.00	1.20	0.15	46.44			
	RHS	1	271.00	1.20	0.15	48.78			
	Marison Layout								
	Chef Bakers Road(LHS)	2	101.00	1.20	0.15	36.36			
	Bharani Medical Store Road	2	206.00	1.20	0.15	74.16			
	Culvert								
	Culvert 8th Crs	1	11.60	1.50	0.15	2.61			

No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Culvert 7th Crs	1	7.50	1.50	0.15	1.69			
	Culvert 6th Crs	1	7.90	1.50	0.15	1.78			
	Culvert 5th Crs	1	7.85	1.50	0.15	1.77			
	Culvert 4th Crs	1	8.00	1.50	0.15	1.80			
	Culvert 3rd Crs	1	7.60	1.50	0.15	1.71			
	Culvert 2nd	1	6.70	1.50	0.15	1.51			
	Culvert 1st	1	7.40	1.50	0.15	1.67			
	Culvert	1	7.00	1.50	0.15	1.58			
						337.76	Cum	5421.90	1831294.17
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications do- Wall & bottom thickness 15cm (I No-37.59.2, P No-271)								
	CC Drain Raft								
	1st Cross frm AGB Layout mn Rd to SWD (LHS)								
	LHS	1	316.00	0.90	0.15	42.66			
	RHS	1	328.00	0.90	0.15	44.28			
	1st Cross frm AGB Layout mn (RHS Up to Dead End)								
	LHS	1	258.00	0.90	0.15	34.83			
	RHS	1	271.00	0.90	0.15	36.59			
	Marison Layout								
	Chef Bakers Road(LHS)	2	101.00	0.90	0.15	27.27			
	Bharani Medical Store Road	2	206.00	0.90	0.15	55.62			
	Culvert								
	Culvert 2nd	1	6.70	0.90	0.15	9.05			
	CC Drain Wall								
	1st Cross frm AGB Layout mn Rd to SWD (LHS)								
	LHS	2	316.00	0.15	0.60	56.88			
	RHS	2	328.00	0.15	0.60	59.04			
	1st Cross frm AGB Layout mn (RHS Up to Dead End)								
	LHS	2	258.00	0.15	0.60	46.44			
	RHS	2	271.00	0.15	0.60	48.78			
	Marison Layout								
	Chef Bakers Road(LHS)	4	101.00	0.15	0.60	36.36			
	Bharani Medical Store Road	4	206.00	0.15	0.60	74.16			
	Culvert								
	Culvert 2nd	1	6.70	0.23	0.20	0.31			
						572.26	Cum	7070.20	4045979.93
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio(I No-28.8.2, P No-229)								
	Consider 65kg/Cum	1	572.26	75.00		42919.37			

[illegible]

No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	For Culverts								
	Culvert 8th Crs	1	11.60	1.50		17.40			
	Culvert 7th Crs	1	7.50	1.50		11.25			
	Culvert 6th Crs	1	7.90	1.50		11.85			
	Culvert 5th Crs	1	7.85	1.50		11.78			
	Culvert 4th Crs	1	8.00	1.50		12.00			
	Culvert 3rd Crs	1	7.60	1.50		11.40			
	Culvert 2nd	1	6.70	1.50		10.05			
	Culvert 1st	1	7.40	1.50		11.10			
						96.83	Sqm	5241.00	507459.83
9	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification No.301 Loading and unloading with 10km lead= (I No-19.14,P No-143)								
	1st Cross frm AGB Layout mn (RHS Up to Dead End)	1	215.00	10.00	0.25	537.50			
						537.50	Cum	69.06	37,119.75
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications (I No-19.64,P No-147)								
	1st Cross frm AGB Layout mn (RHS Up to Dead End)	1	215.00	10.00		2150.00			
						2150.00	Sqm	6.36	13,674.00
11	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	1st Cross frm AGB Layout mn (RHS Up to Dead End)	1	215.00	10.00	0.150	322.50			
						322.50	Cum	1994.92	643361.70
12	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	1st Cross frm AGB Layout mn (RHS Up to Dead End)	1	215.00	10.00	0.225	483.75			
						483.75	Cum	2001.28	968119.20

[illegible]

SI No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
			3,70,000 = 00					DPR & PMC Cost 2%	335000.00
			1,99,99,867 = 30					Sub Total	19985234.87
			132 = 70					Utility Shifting, Miscellaneous and Rounding off	14,765.13
								GRAND TOTAL	20000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR, Bangalore circle for year 2018-2019 and Data Rates




Assistant Engineer
Ward No-12
BBMP Bangalore

Asst. Executive Engineer,
Shettyhalli Sub Division
BBMP Bangalore

Executive Engineer,
Dasarahalli Division
BBMP Bangalore

ಸಂ. EE/AS/171/18-19 ದಿನಾಂಕ : 20.02.2019
ರೂ. 20000000 = 00 (Two Hundred
Lakhs only)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರಿತವಾಗಿ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ, ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. CE/D2/TS/193/18-19 ದಿನಾಂಕ : 22/02/2019
ರೂ. 200.00 Lakhs/- (Two Hundred
Lakhs only)
ಈ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಂತರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಆಂತರಿಕ ಸಹಾಯಕರು ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.



CLIENT:	PROJECT	Dwg Title:
BRUHAT BANGALORE MAHANAGARA PALIKE	Improvements to Sapthagiri Collage Main and adjacent Cross roads in Waed No 12 Shettyhalli Sub Division	PLAN
	CC Drain	